



FORKLIFT PORTABLE FRONT AND REAR



SPRING LOAD[©] DYNAMIC CARRIAGE HURRICANE[©] PRESTRETCH CARRIAGE



•SPRING LOADED FILM HOLDER ALLOWS FOR QUICK AND EASY FILM ROLL CHANGES

•**OPTIONAL** HURRICANE PRESTRETCH FILM CARRIAGE DELIVERS UP TO 300% FILM STRETCH

•ALLOWS UP TO 100% FILM STRETCH

•AUTO FILM CUT
•POWER DE-ENERGIZED WHEN CARRIAGE DOOR OPEN FOR OPERATOR SAFETY

•GREATER FILM SAVINGS

SPECIFICATIONS:

CONTROLS
PRODUCTION SPEED
LOAD SIZE
WEIGHT CAPACITY
STRUCTURAL
TURNTABLE DRIVE

TURNTABLE SPEED
CARRIAGE DRIVE

FILM DELIVERY

FILM ROLL
POWER REQ.

•PLC 4" TOUCH SCREEN CONTROLS
•1-40 LPH*
•55"L x 55"W x 90"H (80" Diagonal)
•5000LBS
•WELDED STEEL CONSTRUCTION
•1/2HP SCR DRIVE
•#50 ANSI CHAIN, 20:1 GEARBOX
•36 TABLE SUPPORT WHEELS
•0-15RPM
•1/2HP SCR DRIVE
•#50 ANSI CHAIN, 60:1 GEARBOX
•STANDARD SPRING LOAD[©] DYNAMIC CARRIAGE WITH 100%+ TENSION STRETCH **OR UPGRADE TO** HURRICANE[©] PRESTRETCH FILM CARRIAGE
•20" MACHINE FILM, 3" CORE
•115VAC, 15A, 60Hz- PLUG AND PLAY

SAFETY

•FULLY GUARDED TOWER & MOVING PARTS
•NO PINCH: CARRIAGE ROLLERS- ROTATE OUTWARD
•EMERGENCY STOP BUTTON

OPTIONS

•PRESTRETCH FILM CARRIAGE
•BASE EXTENSION
•LOADING RAMP
•COMBINATION RAMP (For powered hand trucks)
•INTEGRATED SCALE PACKAGE
•SAFETY FENCING
•SAFETY LIGHT CURTAINS

*SUGGESTED LOADS PER HOUR- May vary depending on load sizes, loading/unloading speeds and number of wraps or wrapping pauses on load.