



## SPECIFICATIONS:

### CONTROLS

- FULL COLOR 7" PLC TOUCH SCREEN
- REMOTE CONTROL START

### PRODUCTION SPEED

- 1-20 LPH\*

### LOAD SIZE

- 48"L x 48"W x 53"H (80" Diagonal)

### WEIGHT CAPACITY

- WEIGHT BASED ON FORKLIFT CAPACITY

### STRUCTURAL

- WELDED STEEL CONSTRUCTION

### RING DRIVE

- 1HP AC MOTOR & DELTA 1HP VFD DRIVE
- 20:1 GEARBOX

### RING SPEED

- 0-15RPM

### CARRIAGE DRIVE

- 1/4HP DC MOTOR & DELTA 1HP VFD DRIVE
- #35 ANSI CHAIN, 60:1 GEARBOX

### FILM DELIVERY

- FRICTION CARRIAGE

### FILM ROLL

- 20" MACHINE FILM, 3" CORE

### POWER REQ.

- 115VAC, 15A, 60Hz- PLUG AND PLAY

### SAFETY

- SAFETY DOOR INTERLOCK
- EMERGENCY STOP BUTTON

### ONBOARD PROGRAMS

- RING SPEED CONTROL
- CARRIAGE SPEED CONTROL

### OPTIONS

- SAFETY LIGHT CURTAINS
- SAFETY FENCING